BRUHAT BANGALORE MAHANAGARA PALIKE

Project Division

Draft Tender Schedule(DTS)

Name of work ; Improvement to drain all round the park in ward no ;14 Dasarahalli Zone

Notification Number

Tender form issued to Sri.....Class Registration number.....

Sl No	Description of Work	Unit	Quantity as per Estimate	Rates in Rs. In Figures	Rates in Rs. In Words
1	Earth work excavation by manual means in ordinsry soil involving an horizontal throw up to 2 meters and average lift up to 0 50 mtr excavated levelled and sides neatly dressed the disposed earth to be levelled and sides neatly dressed after breaking of clods complete as per specifications	Cum	1443 58		
2	KSRB 4-1.3 Providing and laying in position plain cement concrete of mix1:4 8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @ 0 85 cum and fine aggregtes @ 0 57 cum machine mixed machine mixed concrete laid in layers not exceeding 15 cms thick well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete, as per specifications. (P.13/4.3)	Cum	283 43		
3	KSRB 4.2.2 : Providing and laying in position reinforced cement concrete of Design mix M20 with OPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregtes @ 0.460 cum, with super plasticisers @ 3 liters confirming to is 9103-1999 reafirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation for footings, pedastals, retaining walls, return walls, walls (any thickness) including attached pilasters, columnspillars, posts, struts, buttresses, bed blocks, anchor blocks & plinths etc., including cost of all materials, labour, HOM of machinery, curing, complete but excluding cost of reinforcement as per specifications Specification No. KBS 4 1 4 6	Cum	455.51		
4	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications	Tonne	26.37		
5	Providing and fixing precast covering slab made out of cc 1:2:4 with 10 cm thick and finishing cutting including form work curing including cost of all materials labour hire charges of machinary loading un loading lead and lift transportation etc complete as per tender document	Sqm	1008 99		
6	Providing and fixing precast covering slab 250 mm thick made out of cc 1:2:4 and jelly 20 mm down size with steel reinforcement including form work curing including cost of all materials labour hire charges of machinary loading un loading lead and lift transportation etc complete as per the direction of the Engineer incharge of the work	Sqm	135.00		

Scanned with OKEN Scanner

7	Providing and fixing precast solid cement concrete kerb stones made out of cc 1:2:4 with top and bottom width 114 and 165 mm respectively 400mm high 450 mm in length finishrd with CM 1:3 plastering and finishing cutting including formwork ,curing including cost of all materials labour hire charges of machinary, loading and un loading lead and lift transportation etc complete	Nos	2492.00		
8	Providing two coats after filling the surfaces with synthetic enamyl paint in approved shades on new plastered surfaces with materials labour complete as per specifications	Sqm	392.38		

Executive Engineer,
Project Division, Dasarahalli Zone,
Bruhat Bangalore Mahanagara Palik

Scanned with OKEN Scanner